

CITY OF OAK GROVE MINNESOTA

8" PRODUCTION WELL AND APPURTENANCES
CONSTRUCTION PLANS AND SPECIFICATIONS

ADDENDUM NO. 1


September 19, 2011

TO ALL BIDDERS: The above titled plans, specifications, and contract documents are hereby revised in accordance with the items set forth herein.

This addendum to the plans and specifications is hereby made a part of the contract documents for the above-entitled project, to the same extent as though it were originally contained therein.

All bidders are expected to thoroughly examine each item enumerated herein, regardless of its apparent application(s) and shall be held responsible for furnishing all labor and materials required in the division of the work that the items indicate. Items herein shall take precedence over any clauses which they modify in the contract documents or portions of plans and specifications which they modify or supplement.

Receipt of this addendum must be acknowledged by entering Addendum No. 1 in the space provided on the Bid Form.



Brian D. Miller, P.E.
Project Manager

Addendum No. 1
September 19, 2011

Please make the following changes in the plans and specifications for the above-noted project:

BID SCHEDULE

Replace the bid schedule with the attached bid schedule.

	Bid Schedule Production Well, Addendum #1					
	City of Oak Grove					
Item No.	Item Description	Unit	Qty	Unit Price	Total Price	
	<u>Schedule 1.0 Production Well</u>					
1	Mobilization/Demobilization	LS	1			
2	Drill 12" borehole	LF	225			
3	Furnish and Install 8" Steel Well Casing	LF	225			
4	Drill 7-7/8th inch Open Hole	LF	45			
5	Furnish and Install Grout	CY	3			
6	Furnish and Install Pitless Adapter	EA	1			
7	Develop Well	HR	20			
8	Furnish, Install and Remove Test Pump	LS	1			
9	Test Pump	HR	24			
10	Downhole Video, Color, Articulating, 2 tapes	LS	1			
11	Gamma Log	LS	1			
12	Disinfect, Clean Site and log	LS	1			
	Total - Schedule 1.0 Production Well					\$
	<u>Schedule 2.0 Connect to Well House</u>					
1	Cut in 6X10 Tee	LS	1			
2	10 Inch Valve	LS	1			
3	6 Inch Valve	LS	1			
4	6 Inch Ductile Iron Pipe	FT	75			
	Total - Schedule 2.0 Connect to Well House					\$
	Total - Schedule 1.0 Production Well					\$
	Total - Schedule 2.0 Connect to Well House					\$
	TOTAL OF ALL ESTIMATED PRICES					\$
	Potential Additional Items					
1	4 Inch Screen	LF	45			\$
2	Gravel Pack	CY	2			\$