

CITY OF SHAFER MINNESOTA

QUINLAN LANE AND PUBLIC WORK PAVING  
CONSTRUCTION PLANS AND SPECIFICATIONS

CLARIFICATION NO. 1


June 18, 2008

TO ALL BIDDERS: The above titled plans, specifications, and contract documents are hereby revised in accordance with the items set forth herein.

This addendum to the plans and specifications is hereby made a part of the contract documents for the above-entitled project, to the same extent as though it were originally contained therein.

All bidders are expected to thoroughly examine each item enumerated herein, regardless of its apparent application(s) and shall be held responsible for furnishing all labor and materials required in the division of the work that the items indicate. Items herein shall take precedence over any clauses which they modify in the contract documents or portions of plans and specifications which they modify or supplement.

Receipt of this clarification does not need to be acknowledged by entering on the Bid Form; however return the enclosed fax confirmation sheet to verify receipt of this clarification.



Brian D. Miller, P.E.  
Project Manager

Clarification No. 1  
June 18, 2008

Please note the following clarification to the plans and specifications for the above-noted project:

**SPECIFICATIONS**

1. The second page of the Bid Schedule submitted as part of Addendum No. 1 was inadvertently not included when the Addendum was sent June 13, 2008. The enclosed included both pages of the Bid Schedule to be used when submitting the Bid Form.

**Addendum No. 1 - June, 13 2008**

Project: Bid Schedule for Quinlan Lane & Public Works Paving

Owner: City of Shafer, MN

Item No.	Item Description	Unit	Qty.	Unit Price	Amount
<b><u>SCHEDULE 1.0 QUINLAN LANE</u></b>					
2104.501	REMOVE BITUMINOUS PAVEMENT	SY	360		
2104.509	REMOVE CMP CULVERT	EA	3		
2104.513	SAWING BITUMINOUS PAVEMENT	LF	190		
2105.501	COMMON EXCAVATION	CY	309		
2105.507	SUBGRADE EXCAVATION	CY	175		
2105.522	SELECT GRANULAR BORRW (CV)	CY	175		
2105.525	TOPSOIL BORROW (LV)	CY	132		
2105.601	SITE GRADING	LS	1		
2111.501	TEST ROLLING	Rd. Sta	6.4		
2112.501	SUBGRAGE PREPARATION	Rd. Sta	6.4		
2211.501	AGGREGATE BASE CLASS 5	TN	804		
2232.501	MILL BITUMINOUS SURFACE	SY	72		
2350.501	TYPE MV3 WEARING COURSE MIXTURE (B)	TN	102		
2350.503	TYPE LV3 NON WEARING COURSE MIXTURE (B)	TN	204		
2357.502	BITUMINOUS MATERIAL FOR TACK COAT	GAL	93		
2501.511	12" CS PIPE CULVERT	LF	85		
2501.511	15" RC PIPE CULVERT CL V	LF	43		
2501.515	12" CS PIPE APRON	EA	6		
2501.515	15" RC PIPE APRON	EA	2		
2504.602	ADJUST VALVE BOX	EA	2		
2506.522	ADJUST FRAME AND RING CASTING	EA	4		
2511.501	RANDOM RIPRAP, CLASS III	CY	6		
2531.501	CONCRETE CURB AND GUTTER, DEIGN S412	LF	316		
2563.601	TRAFFIC CONTROL	LS	1		
2573.502	SILT FENCE, TYPE PREASSEMBLED	LF	560		
2573.530	STORM DRAIN INLET PROTECTION	EA	4		
2575.501	SEEDING	AC	0.5		
2575.505	SODDING TYPE LAWN	SY	340		
2575.523	EROSION CONTROL BLANKET, CATEGORY 3	SY	250		
2575.604	GEOTEXTILE FABRIC	SY	200		
2582.502	4" SOLID LINE WHITE - EPOXY	LF	1300		
2582.502	4" DOUBLE SOLID LINE YELLOW - EPOXY	LF	638		
	SPEC. SUBGRADE PROCTOR TEST	EA	4		
	SPEC. SUBGRADE DENSITY TEST, INPLACE	EA	10		
	SPEC. CLASS 5 PROCTOR TEST	EA	2		
	SPEC. CLASS 5 GRADATION TEST	EA	2		
	SPEC. CLASS 5 DENSITY TEST, INPLACE	EA	4		
<b>TOTAL - SCHEDULE 1.0 QUINLAN LANE</b>					<hr/>

Item No.	Item Description	Unit	Qty.	Unit Price	Amount
----------	------------------	------	------	------------	--------

**SCHEDULE 2.0 PUBLIC WORKS**

2105.522	SELECT GRANULAR BORRW (CV)	CY	148		
2112.604	SUBGRAGE PREPARATION	SY	443		
2211.501	AGGREGATE BASE CLASS 5	TN	140		
2232.501	MILL BITUMINOUS SURFACE	SY	291		
2350.501	TYPE MV4 WEARING COURSE MIXTURE (B)	TN	37		
2350.503	TYPE LV3 NON WEARING COURSE MIXTURE (B)	TN	73		
2357.502	BITUMINOUS MATERIAL FOR TACK COAT	GAL	20		
2511.515	GEOTEXTILE FABRIC, TYPE 5	SY	443		
2573.502	SILT FENCE, TYPE PREASSEMBLED	LF	190		
2575.501	SEEDING	AC	0.22		

**TOTAL - SCHEDULE 2.0 PUBLIC WORKS**

**ALTERNATE SCHEDULE 3.0 PUBLIC WORKS LANDSCAPING**

2511.515	GEOTEXTILE FABRIC, TYPE 5	SY	95		
2540.604	INSTALL LANDSCAPING ROCK	SY	95		

**TOTAL - ALTERNATE SCHEDULE 3.0 PUBLIC WORKS LANDSCAPING**

**PROJECT SUMMARY**

**SCHEDULE 1.0 QUINLAN LANE**

**SCHEDULE 2.0 PUBLIC WORKS**

**TOTAL BID PRICE**

**TOTAL BID PRICE WITH ALTERNATE**