

CITY OF OAK GROVE, MINNESOTA
NORTHEAST SEWER IMPROVEMENTS
CONSTRUCTION PLANS AND SPECIFICATIONS


ADDENDUM NO. 3
JUNE 24, 2009

TO ALL BIDDERS: The above titled plans, specifications, and contract documents are hereby revised in accordance with the items set forth herein.

This addendum to the plans and specifications is hereby made a part of the contract documents for the above-entitled project, to the same extent as though it were originally contained therein.

All bidders are expected to thoroughly examine each item enumerated herein, regardless of its apparent application(s) and shall be held responsible for furnishing all labor and materials required in the division of the work that the items indicate. Items herein shall take precedence over any clauses which they modify in the contract documents or portions of plans and specifications which they modify or supplement.

Receipt of this addendum must be acknowledged by entering Addendum No. 3 in the space provided on the Bid Form.



Brian Miller, P.E.
Project Manager

Please make the following changes in the plans and specifications for the above-noted project:

SPECIFICATION

1. Replace the Bid Schedule with the enclosed. Noted change are as follows:
 - a. The quantity for Item 2104.501 Remove Bituminous Pavement has been changed from 8,064 square yards to 869 square yards.
 - b. The quantity for Item 2350.501 Type MV3 Wearing Course Mixture (B) has been changed from 9.5 tons to 7.1 tons.
 - c. The quantity for Item 2350.503 Type LV3 Non-Wearing Course Mixture (B) has been changed from 7.1 tons to 9.5 tons.

2. Replace Part 2.08E of Section 11311 Submersible Sewage Pumps with the following:

“E. Motors shall be 240 Volt, Single-phase, 60-cycle.”

PLANS

3. Revise the casting note on the “Typical Slab Top Manhole” detail on Sheet 12 to read:
“Provide Frost Retardant Casting; Neenah R1758 Series or Municipal Castings Model 309 with minimum inside opening of 22 inches”

ATTACHMENTS

1. Addendum No. 3 Bid Schedule – June 24, 2009

NOTE:

Advertisements, Addenda and Plan Holder Lists can be obtained at www.bdmce.com.

Project: Bid Schedule for Northeast Sewer Forcemain

Owner: City of Oak Grove, MN

Addendum No. 3 Bid Schedule - June 24, 2009

Item No.	Item Description	Unit	Qty.	Unit Price	Amount
<u>SCHEDULE 1.0 Northeast Sewer Forcemain</u>					
2104.501	REMOVE BITUMINOUS PAVEMENT	SY	896		
2104.513	SAWING BITUMINOUS PAVEMENT	LF	371		
2104.525	ABANDON GROUND WATER MONITORING WELL	EA	2		
2105.522	SELECT GRANULAR BORROW (CV)	CY	60		
2105.525	TOPSOIL BORROW (LV)	CY	320		
2211.501	AGGREGATE BASE CLASS 5	TN	24.7		
2350.501	TYPE MV3 WEARING COURSE MIXTURE (B)	TN	7.1		
2350.503	TYPE LV3 NON WEARING COURSE MIXTURE (B)	TN	9.5		
2357.502	BITUMINOUS MATERIAL FOR TACK COAT	GAL	52		
2573.502	SILT FENCE, TYPE PREASSEMBLED	LF	203		
2575.501	SEEDING	AC	0.59		
	SPEC. LIFT STATION PUMPS REPLACEMENT	LS	1		
	SPEC. LIFT STATION ELECTRICAL	LS	1		
	SPEC. CONNECT TO EXISTING FORCEMAIN SEWER	EA	2		
	SPEC. 6" M.J. GATE VALVE	EA	3		
	SPEC. 6" HDPE FORCEMAIN	LF	9,354		
	SPEC. STANDARD CLEANOUT MANHOLE	EA	3		
	SPEC. STANDARD 90° CLEANOUT MANHOLE	EA	3		
	SPEC. COMBINATION AIR/VAC/CLEANOUT MANHOLE	EA	4		
	SPEC. COMBINATION 90° AIR/VAC/CLEANOUT MANHOLE	EA	1		
	SPEC. SPECIAL MANHOLE NO. 12	EA	1		
	SPEC. ARRA PROJECT SIGN	LS	1		
TOTAL BID PRICE					